MYSORE DIVISION.

Notification dated 20th December 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on 18th January 1936 (Saturday), for "Improving the capacity of Maddanahatti Tank, Register No. 28, Nagamangala Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 230 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving the capacity of Muddanahatti Tank, Register No. 28, of Nagamangala Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for improving the capacity of Maddanahatti Tank, Register No. 28, Nagamangala Taluk.

Serial No.	Items of work	Per	Rate	Quantity	Cost
	BUND.		Rs. a. p.		
	Raising the Bund from R.L. 56·00 to 58·00.				
1	Earthwork excavation for seat of bund ..	C.yd.	0 3 0	51	
2	Earthwork with watering and tamping ..	,,	0 4 6	6,456	
3	Rough stone revetment with jelly backing ..	,,	1 12 0	428	
4	Gravel backing to revetment	,,	0 8 0	217	
5	Turfing to slopes	Sqr.	0 10 0	538	
6	Providing and fixing index stones	Each	1 0 0	21	
7	Do Grade stones with bed slabs including cutting figures and painting	,,	3 0 0	1	
8	Removing and refixing gauge stones to plumb with necessary masonry works including painting	,,	5 0 0	1	
9	Removing and refixing grade stones	,,	0 4 0	20	
	Waste Weir to be raised from R. L. 50·00 to 52·00				
1	Removing and resetting coping slab	S.ft.	0 2 0	285	
2	Providing and fixing 6" thick burnt stone slab ..	,,	0 7 0	5	
3	Burnt brick in surki mortar	C.ft.	0 4 6	1,757	
4	Surki mortar plastering	Sqr.	4 0 0	9·6	
5	Size stone in surki mortar	C.ft.	0 5 6	16	
6	Cement concrete, 1 : 2 : 4	,,	0 12 0	23	
7	½" thick cement plaster 1: 2	Sqr.	10 0 0	5·52	
8	Burnt stone bond slabs	Lumpsum	45 0 0		
9	Cushion	,,	75 0 0		
10	Raising the training bank—				
	(*a*) Earthwork with watering and tamping ..	C.yd.	0 4 6	35	
	(*b*) Rough stone revetment, new	,,	1 12 0	5	
	(*c*) Turfing to slopes	Sqr.	0 10 0	5·50	

V. V. PATANKAR,
Executive Engineer.